Contents

Acknowledgments . . . . . **ix**
Abbreviations and Acronyms . . . . . **xi**
Foreword: A Message for School Boards and Administrators . . . . . **xv**

Chapter 1 **Introduction** **1**
Goal of this Guide 2
Scope 2
Energy Modeling Analysis 3
Achieving 50% Energy Savings 4
Conditions to Promote Health and Comfort 5
Indoor Air Quality (IAQ) 5
Thermal Comfort 5
Visual Comfort 6
Acoustic Comfort 6
How to Use this Guide 6
References and Resources 7

Chapter 2 **Integrated Design Process** **9**
Principles of Integrated Design 9
Using Integrated Design by Project Phase 12
Project Kickoff 12
Programming and Concept Design 13
Schematic Design 14
Design Development 16
Construction Documents 16
Bid Phase 21

Construction 21
Commissioning 22
Operations and Maintenance 22
Post Occupancy Operations: The Building as a Teaching Tool. 23
Integrated Design Best Practices. 23
Building Site and Design Influences 23
Multidisciplinary Coordination for Energy Efficiency 31
References and Resources. 40

Chapter 3 **Performance Targets and Case Studies. 43**
Energy Targets 43
References and Resources. 46
Case Studies 46
Gloria Marshall Elementary School 46
Marin County Day School. 49
Manassas Park Elementary School and Prekindergarten. 51
Richardsville Elementary School 54
Greensburg K-12 School 58
Kinard Junior High School 60
Two Harbors High School 62
References and Resources. 65

Chapter 4 **Design Strategies and Recommendations by Climate Zone 67**
Introduction. 67
Climate Zone Recommendations 69
Zone 1 70
Zone 2 73
Zone 3 76
Zone 4 79
Zone 5 82
Zone 6 85
Zone 7 88
Zone 8 91

Chapter 5 **How to Implement Recommendations 95**
Envelope 95
Opaque Envelope Components 95
Vertical Fenestration 106
Window Design Guidelines for Thermal Conditions 108
Daylighting 110
General Recommendations 110
Classroom Sidelighting Strategies. 122
Classroom Toplighting Strategies 127
Classroom Sidelighting Plus Toplighting Strategies 130

Gym Toplighting Strategies . . . 131
References and Resources . . . 133
Electric Lighting . . . 134
Interior Lighting . . . 134
References and Resources . . . 152
Exterior Lighting . . . 152
References and Resources . . . 154
Plug Loads . . . 154
Equipment and Control Guidelines . . . 154
References and Resources . . . 157
Kitchen Equipment . . . 157
Equipment and Design Guidelines . . . 157
References and Resources . . . 161
Service Water Heating . . . 162
General Recommendations . . . 162
References and Resources . . . 164
HVAC . . . 165
HVAC System Types . . . 165
HVAC System Considerations . . . 171
References and Resources . . . 185
Quality Assurance . . . 187
Commissioning . . . 187
Measurement and Verification (M&V) . . . 190
Teaching Tools . . . 191
References and Resources . . . 193
Additional Bonus Savings . . . 194
Other HVAC Strategies . . . 194
References and Resources . . . 198
Renewable Energy . . . 198
References and Resources . . . 202

Appendix A **Envelope Thermal Performance Factors . . . 203**

Appendix B **International Climatic Zone Definitions . . . 205**
Definitions . . . 206
References . . . 206

Appendix C **Commissioning Information and Examples . . . 207**
Commissioning Scope of Services . . . 207
Introduction . . . 208
Systems . . . 208
Deliverables . . . 208
Schedule . . . 208
Commissioning Tasks . . . 209

Sidebars—Case Studies and Technical Examples

Chapter 2	Operating as an Integrated Design Team	11
	Energy Goals By Design Phase Checklist	18
	Cost Control Strategies and Best Practices	32
	Key Design Strategies for Controlling Capital Costs	34
	Green Design on a Budget	36
Chapter 4	Bonus Savings	69
Chapter 5	Insulated Concrete Form Exterior Wall Assembly	98
	Benefits of Daylighting	111
	Examples of Daylighting Strategies in K-12 School Spaces	115
	Shading Strategy Examples	119
	Compatibility between Daylighting and Audiovisual Projection	120
	Using Baffles in Roof Monitors	129
	BEF-P Calculation	136
	ASHRAE/IES Standard 90.1-2010 Occupancy Sensor Requirements	139
	Locating Ground-Source Heat Pumps	167
	Two-Stage or Variable-Speed Compressors	168
	Variable-Air-Volume/Dedicated Outdoor Air System	171
	Demand-Controlled Ventilation	179
	Teaching Tools	192
	Thermal Energy Storage	196